

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21699-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 12-22S-23W
1245 feet from N Section Line, 1496 feet from W Section Line
Lease Name: ALOHA Well #: 1
County: HODGEMAN Total Vertical Depth: 4630 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	236		WITH 280 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/28/2011 10:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: SAM STAGGS Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 04/28/2011 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAY -- 4 2011
KCC DODGE CITY

RECEIVED
Form CL 073
MAY 09 2011
KCC WICHITA