

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20888-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 30-5S-36W  
431 feet from S Section Line, 1776 feet from W Section Line  
Lease Name: BRINEY TRUST Well #: 1  
County: RAWLINS Total Vertical Depth: 5000 feet

Operator License No.: 30742

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	432		270 SX

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH ST  
NEWTON, KS 67114

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/25/2010 7:15 AM

Plug Co. License No.: 33575

Plug Co. Name: WW DRILLING, LLC

Proposal Rcvd. from: JAY

Company: PALOMINO PETROLEUM, INC.

Phone: (316) 799-1000

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER

Witness Type: NONE

Date/Time Plugging Completed: 09/25/2010 9:30 PM

KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 3135' w/25 sxs.  
2nd. Plug at 2250' w/100 sxs.  
3rd. Plug at 480' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher  
(TECHNICIAN)

RECEIVED

MAY 09 2011

KCC WICHITA

MAY 04 2011

Form CP-2/3

CM