

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20930-00-00
Spot: E2NWNENE Sec/Twnshp/Rge: 21-12S-32W
4950 feet from S Section Line, 750 feet from E Section Line
Lease Name: YOUNKIN Well #: 2
County: LOGAN Total Vertical Depth: 4637 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4558		
SURF	10.75	231	0	200 SX
PROD	5.5	4633	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2011 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: WILLIAM "BILL" BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 259-1297

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2011 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

10 3/4" surface casing set at 231' w/200 sxs cement.
5 1/2" production casing set at 4633' w/150 sxs cement.
Lost circulation squeezes: 2458' w/300 sxs - 2480' w/400 sxs - 2480' w/300 sxs - 2200'-2400' w/250 sxs - 2200'-2400' w/250 sxs.
DV Tool at 2602' w/450 sxs cement - did not circulate.
Perforated production casing at 1822' cemented with 250 sxs cement- cement circulated to surface.
Perforations: 4551' - 4555' and 4572' - 4576'.
Connected to 5 1/2" production casing - pumped 75 sxs cement mixed with 300# hulls - followed with 12 sxs gel and 275 sxs cement.
Max. P.S.I. 800#. S.I.P. 700#.
10 3/4" surface casing full of cement.

Perfs:

Top	Bot	Thru	Comments
4572	4576		MORROW
4570	4575		JOHNSON
4560	4564		JOHNSON
4551	4555		JOHNSON
4360	4364		MARMINTON
4280	4284		KANSAS CITY
4226	4230		LANSING
4176	4180		LANSING
1950			

Remarks: CONSOLIDATED OIL WELL SERVICES LLC-TICKET #30,745.

Plugged through: CSG

RECEIVED
MAY 02 2011
KCC WICHITA

District: 04

Signed Darrel Dipman
(TECHNICIAN) *CM*

APR 25 2011