

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26133-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 13-13S-19W
1180 feet from S Section Line, 1520 feet from E Section Line
Lease Name: ALMA HERL Well #: 1-13
County: ELLIS Total Vertical Depth: 3753 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/28/2011 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO INC Phone: (785) 621-2610

Proposed Plugging Method: Ordered 245 sxs 6040 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 04/28/2011 3:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3640' w/25 sxs.
2nd. Plug at 1375' w/25 sxs.
3rd. Plug at 800' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
MAY 02 2011
KCC WICHITA

District: 04

Signed Case Morris
(TECHNICIAN)