

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21046-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 24-13S-30W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WECKEL Well #: 1
County: GOVE Total Vertical Depth: 4600 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 308 | 0 | 225 sx |
| PROD | 5.5 | 4600 | 0 | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2011 9:30 AM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (316) 262-1719

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls - 13 sxs gel.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2011 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 308' w/225 sxs cement.
5 1/2" production casing set at 4600' w/100 sxs cement.
TD 4600'. PBTD 4556'. DV Tool at 2295' w/600 sxs.
Ran tubing to 4330' - pumped 13 sxs gel - followed with 50 sxs cement mixed with 150# hulls.
Pulled tubing to 2330' - pumped 110 sxs cement mixed with 150# hulls.
Pulled tubing to 1200' - pumped 110 sxs cement mixed with 100# hulls - cement to surface.
Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 15 sxs cement.
Connected to 8 5/8" surface casing - pumped 6 sxs cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 4532 | 4537 | | MISSISSIPPI |

Remarks: ALLIED CEMENTING COMPANY-TICKET #43,343.

Plugged through: TBG

RECEIVED

MAY 02 2011

KCC WICHITA

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

Form CP-2/3

APR 25 2011