

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03943-00-00
Spot: NENENE Sec/Twnshp/Rge: 24-17S-11W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: PETERMAN Well #: 6
County: BARTON Total Vertical Depth: 3298 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	624	0	375 SX
PROD	5.5	3286	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2011 12:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1350' - 650' - 200'.
Unknown junk in the well at 1500'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2011 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1500' - could not get down.
Pulled tubing to 1490' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 500' - pumped 135 sxs cement with 100# hulls.
Cement circulated out the Braden head.
POOH. Hooked onto casing and pumped 20 sxs cement.
Max. P.S.I. 150# - circulated out the Braden head.

Perfs:

Top	Bot	Thru	Comments
3011	3189		LKC

Remarks: QUALITY WELL SERVICE-TICKET #5145.

Plugged through: TBG

RECEIVED

MAY 02 2011

KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

APR 22 2011