

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03939-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 24-17S-11W  
3630 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: PETERMAN A Well #: 1  
County: BARTON Total Vertical Depth: 3295 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	293	0	165 SX
PROD	7	3276	0	75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2011 5:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 365 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2011 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

04/14/2011 - Witnessed by Bruce Rodie:  
Perfed at 1380' - 615' - 250'.  
Ran tubing to 3100' - tied to tubing - pumped 50 sxs cement with 200# hulls.  
Pulled tubing to 2600' - tied to tubing - pumped 10 sxs gel.  
Pulled tubing to 1900' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1400' - pumped 230 sxs cement with 100# hulls - lost circulation at 200 sxs - pumped 30 more sxs cement - shut down for the day.  
04/18/2011 - Witnessed by Ray Dinkel:  
Ran tubing and tagged at 850'.  
Pulled tubing to 830' - pumped 150 sxs cement with 200# hulls - cement circulated.  
POOH. Hooked up to casing - pumped 20 sxs cement.  
Max. P.S.I. 500#.  
Hooked up to Braden head - pumped 15 sxs cement.  
Max. P.S.I. 200#.  
Finished at 11:00AM.

Remarks: QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED  
MAY 02 2011  
KCC WICHITA

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN)

CM

Form CP-2/3

APR 22 2011