


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15:05:04 3:00:00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 4 Twp. 13S Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. NE SW NW
Lease Owner Frontier Oil Company
Lease Name Wolf Well No. 1
Office Address 580 Fourth National Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed December 30, 1958 19 58
Application for plugging filed December 30 19 58
Application for plugging approved December 30 19 58
Plugging commenced December 30 19 58
Plugging completed December 30 19 58
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set bottom plug
At 550'. Put 20 sacks cement through drill pipe.
Filled with heavy mud to 155'. Set middle plug
@ 155'. Put 15 sacks of cement on middle plug.
Set top plug @ 40'. Filled to base of cellar with
1/2 sack Hulls and 10 sacks of cement.

ST: _____
JAN 16 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 Russell, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
George A. Angle (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth National Bank Building-Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1958

My commission expires 11-17-58 _____
Notary Public.

PLUGGING
FILE SEC 4 T. 13 R 17
BOOK PAGE 73L E 32

DRILLERS LOG

No. 1 Wolf

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:	NE SW NW
8-5/8" @ 207	CONTRACTOR:	Red Tiger Drilling Co.	4-13S-17W	Ellis
w/135 sx cement	COMMENCED:	December 19, 1957	County	Kansas
	COMPLETED:	December 29, 1957	ELEVATION:	2069 DF
TOTAL DEPTH:	3730 (-1658)			2072 RB

15-051-04013-00-00

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay and Shells	0	100	
Blue Shale and Shells	100	205	
Shale and Shells	205	505	
Sand	505	920	
Redbed and Shells	920	1269	
Anhydrite	1269	1300	
Shale and Shells	1300	2055	
Lime and Shale	2055	2410	
Shale and Shells	2410	2560	
Shale and Lime	2560	2760	
Shale and Shells	2760	3050	
Lime and Shale	3050	3195	
Lime	3195	3592	
Conglomerate	3592	3716	
Arbuckle Total Depth	3716	3730	

STATE OF KANSAS

JAN 16 1958

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 15th day of January, 1957.

Mapine Head
Notary Public

My Commission Expires:

11-17-58

LOG
4-13S-17W
BORN 73 JUL 32