

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-051-06730-00-00

API NUMBER 4-29-55

LEASE NAME Walters

WELL NUMBER # 2

330' Ft. from S Section Line  
2,310' Ft. from E Section Line

SEC. 4 TWP. 13 RGE. 17 (X) or (W)

COUNTY Ellis

Date Well Completed 4-29-55

Plugging Commenced 2-27-90

Plugging Completed 2-27-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Isis Operating, Inc.

ADDRESS Box 423 Russell, Ks. 67665

PHONE# (913) 483-4092 OPERATORS LICENSE NO. 8240

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-26-90 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3,566' Bottom 3,598' T.D. 3,598'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	3,566'	3,598'	5 1/2"	3,586'	None
Lansing-KC	Oil, water, gas	3,334'	3,338'	8 5/8"	195'	None
				8 5/8" x 5 1/2"	annulus- with 100	cemented from 304'-1075' sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from     feet to     feet each set  
Perforated Anhydrite formation with 2 jet holes at 1,250' and below the Dakota formation at 730' with 2 jet holes. Fluid level in the casing was at 970' from the surface. Pumped down the 5 1/2" casing with 235 sacks of 60-40 Pozmix cement, 8% gel and 500# of cottonseed hulls. Max. pressure 700# and SI 425#. Pumped annulus with 25 sacks of 60-40 Pozmix cement. Max  
 (If additional description is necessary, use BACK of this form.)

pressure 0#. Left annulus full of cement. Had small leak in 8" below casinghead.  
 Name of Plugging Contractor Halliburton Services License No.    

Address Hays, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Isis Operating, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

James R. Line (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) James R. Line

(Address) 29 Ober St. Russell, Ks. 67665

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 90

Pamela Gayle Anschutz  
 Pamela Gayle Anschutz  
 Notary Public

My Commission Expires: 4/23/90



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas

**COPY**

15-051-06730-0000


Company- GRAHAM-MESSMAN-RINEHART DRILLING CO.  
Farm- Walter "A" No. 2

SEC. 4 T. 13 R. 17W  
SW SW SE

Total Depth. 3598  
Comm. 4-20-55 Comp. 4-29-55

County Ellis KANSAS

Shot or Traced.  
Contractor. Graham-Messman-Rinehart Oil Co.  
Issued, 6-18-55



CASING:

8 5/8" 195' com. w/120 sxc  
5 1/2" 3586' com. w/75 sxc

Elevation. 2054 KB

Production. 25 bbls. oil

Figures indicate Bottom of Formations.

sand & clay	150
shale	400
shale & sand	775
Dakota sand	875
shale & sand	905
redbed & shale	1234
Anhydrite	1278
redbed & shale	1565
shale & shells	1665
salt	1840
shale & lime	2775
shale	2825
shale & lime	3270
lime	3485
lime & shale	3500
lime	3586 RTD
lime	3598
Total depth	

15-051-06730-00-00

Sample Tops:	
Anhydrite	1234
Hoebner	3265
Toronto	3284
Lansing	3330
Arbucklo	3566

MAR 02 1990