

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-06729-00-00

API NUMBER 2-11-55

LEASE NAME Walters

WELL NUMBER # 7

990' Ft. from S Section Line

2,310' Ft. from E Section Line

SEC. 4 TWP. 13 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 2-11-55

Plugging Commenced 7-10-90

Plugging Completed 7-11-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Isis Operating, Inc.

ADDRESS Box 423 Russell, KS. 67665

PHONE# (913) 483-4092 OPERATORS LICENSE NO. 8240

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-10-90 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3,572' Bottom 3,577' T.D. 3,577'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	3,572'	3,577'	8 5/8"	190'	None
Lansing-KC	Oil, water, gas	3,341'	3,351'	5 1/2"	3,574'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran 1" line pipe to 1,315'. Pumped down 1" with 50 sx of common cement followed by 260 sx of 65-35 Pozmix cement, 8% gel, and 600 # of cottonseed hulls at 0-100 PSI. Had cement to the surface between 8 5/8" and 5 1/2" casing strings. Pumped 90 sx of 65-35 Pozmix cement, 8% gel, and 400 # hulls down annulus between 1" and 5 1/2" casing strings at 0-100 PSI. Waited 1 hour.
 (If additional description is necessary, use BACK of this form.) (continued on back)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Isis Operating, Inc. STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Russell, ss.

James R. Line (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James R. Line

(Address) 29 Ober St. Russell, KS. 67665



AND SWORN TO before me this 13th day of July, 1990

Pamela Gayle Anschutz
 Notary Public

My Commission Expires: 4-23-94

Pressured tubing and casing to 200 PSIG and held. Closed in overnight. Cut
off 8 5/8" and 5 1/2" casing, both full of cement.



WELL RECORD

15-051-06729-00-00

Location: NW SW SE, 4-13S-17W
 Ellis County, Kansas

Operator: Graham-Messman-Rinehart Oil Company
 1005 East Second, Wichita, Kansas

Contractor: Graham-Messman-Rinehart Drilling Co.
 1005 East Second, Wichita, Kansas

Casing Record: 8 5/8" @ 190' w/115 sacks cement
 5 1/2" @ 3574' w/75 sacks cement

Commenced: November 15, 1954

Completed: November 25, 1954

Elevation: 2060 KB

Productions:

....L O G....

Clay	60
Shale	470
Sand	570
Shale-Sand	775
Salt	885
Red Bed-Sand	980
Red Bed-Shale	1250
Anhydrite	1296
Shale-Shells	1355
Shale-Red Bed	1475
Shale	1580
Salt	1750
Shale-Shells	1900
Lime-Shale	2086
Shale-Lime	2255
Pyrite-Shale	2280
Lime	2295
Lime-Shale	2450
Shale-Lime	2695
Shale-Shells	2623
Lime	2735
Shale-Lime	3045
Lime	3270
Lime-Shale	3320
Lime	3572
Arbuckle	3577 R.T.D.

Heobner 3274 (-1214)
 Lansing 3320 (-1260)
 Arbuckle 3572 (-1512)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: Signed by J. A. Gilliland
 J. A. Gilliland

Subscribed and sworn to before me this
 15th day of December 1954.

Signed by Janita L. Povic
 Notary Public

Commission Expires: November 5, 1958

RECEIVED
 STATE COMMISSION

JUL 16 1990

CONSERVATION DIVISION
 Wichita, Kansas