


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-051-22382-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 4 Twp. 13S Rge. 17W E/W
Location as "NE/CNW/SW" or footage from lines
SE NE SE

Lease Owner A & A Oil Company
Lease Name TOM WOLTERS Well No. #1
Office Address 2522 Felton Drive, Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed May 13 1981
Application for plugging filed May 13 1981
Application for plugging approved May 13 1981
Plugging commenced May 13 1981
Plugging completed May 13 1981

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3595
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

T.D. @ 3595'

Set 1st Plug @ 740' with 65 sacks

Set 2nd Plug @ 240' with 30 sacks

Set 3rd Plug @ 40' Solid Bridge with 10 sacks, 5 sacks in rathole

50-50 posmix, 6% gel.

RECEIVED

STATE CORPORATION COMMISSION

JUN 15 1981

Job completed @ 9:15 a.m., 5/13/81.

State Plugger - Marion Schmidt.

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)


Jack L. Partridge

801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1981

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



CONTRACTOR'S WELL LOG

15-051-22382-00-00

OPERATOR: A & A Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: TOM WOLTERS #1
 LOCATION: SE NE SE, Section 4-13S-17W
 Ellis County, Kansas
 SPUD DATE: 5/06/81
 COMPLETION DATE: 5/13/81

0	210	Clay, Sand & Shale
210	1565	Sand & Shale
1565	1944	Shale, Sand & Lime
1944	2205	Shale
2205	3595	Shale & Lime
	3595	Rotary Total Depth

Spud @ 7:45 p.m., 5/06/81. Drilled 210' of a 12 1/4" hole. Ran 6 joints of 8-11/16", 20# surface casing (tally 200.63') Set @ 207.13'. Cemented with 150 sx. of common 2% gel, 3% c.c. Plug was down @ 2:30 a.m., 5/07/81. Cement did circulate. Waiting on cement.

T.D. @ 3595'. Set 1st Plug @ 740' with 65 sacks, Set 2nd Plug @ 240' with 30 sacks, Set 3rd Plug @ 40' Solid Bridge with 10 sacks, 5 sacks in rathole, 50-50 posmix, 6% gel. State Plugger - Marion Schmidt. Cement by Sun Cement. Job was completed @ 9:15 a.m., 5/13/81.

SAMPLE TOPS:

Anhydrite 1237'
 B/Anhydrite 1271'

RECEIVED
 STATE CORPORATION COMMISSION

JUN 15 1981

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the TOM WOLTERS #1, SE NE SE, Section 4-13S-17W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC:

BY: Jack L. Partridge
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 11th day of June, 1981.



Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public