

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-4  
March 2009

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING RECORD  
K.A.R. 82-3-117

OPERATOR: License #: 31203  
Name: McQuade, Owen dba Owen's Pumping Service  
Address 1: 640 E. Sunset Ave  
Address 2: \_\_\_\_\_  
City: Russell State: KS Zip: 67665 + \_\_\_\_\_  
Contact Person: Owen McQuade  
Phone: (785) 483-6321  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 053-21262-00-00  
Spot Description: \_\_\_\_\_  
SE  NE  NW  Sec. 19 Twp. 15 S. R. 10  East  West  
1,350 Feet from  North /  South Line of Section  
2,800 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellsworth  
Lease Name: Branda Well #: 2  
Date Well Completed: 5/5/2011  
The plugging proposal was approved on: 4/29/2011 (Date)  
by: Patrick (KCC District Agent's Name)  
Plugging Commenced: 5/5/2011  
Plugging Completed: 5/5/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	400'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 180 sacks 60/40 Poz, 3% gel, 1st plug @ 3230' with 35 sacks, 2nd plug @ 1300' with 35 sacks, 3rd plug @ 950' with 35 sacks, 4th plug @ 450' with 35 sacks, 5th plug @ 60' to surface with 25 sacks, rat hole with 15 sacks, by Quality (Ticket #4902). Plug was down @ 5:15 pm on 5/5/2011.

RECEIVED

MAY 09 2011

KCC WICHITA

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc.  
Address 1: PO Box 276 Address 2: \_\_\_\_\_  
City: Ellinwood State: Kansas Zip: 67526 + \_\_\_\_\_  
Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: McQuade, Owen dba Owen's Pumping Service  
State of Kansas County, Barton, ss.  
Jennifer Heape  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape  
Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SOUTHWIND DRILLING, INC.  
PLUGGING ORDERS AND REPORTS

Lease: Branda #2

Plugging received from KCC representative:

Name: Patrick Wichita KCC Date 4-29-11 Time 9:12 AM

1<sup>st</sup> plug @ <sup>3230'</sup> top Arb ft. 35 sx. Stands: 54 1/2

2nd plug @ 1300 ft. 35 sx. Stands: 21 1/2

3rd plug @ 950 ft. 35 sx. Stands: 16

4th plug @ 450 ft. 35 sx. Stands: 7 1/2

5th plug @ 60' to surface ft. 25 sx. Stands: 1

Mousehole          sx.

Rahole 15 sx.

Total Cement used: 180 sx.

Type of cement 60/40 pos no more than 3% gel by quality

Plug down @ 5:15 p.m 5-5-11

Call KCC When Completed:

Name: Dan Fox Wichita KCC Date may 5 Time 5:00

RECEIVED  
MAY 09 2011  
KCC WICHITA