

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 +
Contact Person: Dennis Kirmer
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Platts Depth to Top: 2916 Bottom: 2926 T.D.
Douglas Depth to Top: 3019 Bottom: 3026 T.D.
LKC Depth to Top: 3064 Bottom: 3143 T.D.

API No. 15 - 167-03291-0000
Spot Description:
N2 SE NW Sec. 16 Twp. 15 S. R. 13 East West
3,960 Feet from North / South Line of Section
1220 3300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Russell
Lease Name: Holland Co Well #: 2
Date Well Completed: 7/1941
The plugging proposal was approved on: (Date)
by: (KCC District Agent's Name)
Plugging Commenced: 4-22-11
Plugging Completed: 4-22-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	10 3/4	200'	
		Production	5 1/2	3064'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate two holes each at 900' and 495'. Run open end tbg to 3115. Rig up Allied Cementing. Mix 100 sxs 60/40 poz 4 % gel w/200# hulls. Pull tbg to 2113. Mix 100 sxs cement w/200# hulls. Pull tbg to 1115. Mix 150 sxs cement w/200# hulls and circulate cement to surface. Pull tbg out of hole. Hook up to 5 1/2 csg. Mix 40 sxs cement and pressure to 150#. Held. Hook up to 10 3/4 surface pipe mix 35 sxs cement and pressure to 100#. shut in. Well plugged 1:00 p.m.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Dennis Kirmer Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

RECEIVED

MAY 10 2011

KCC WICHITA