


WELL PLUGGING RECORD

*Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Gove County, Sec. 15 Twp. 13 Rge. 27W (E) (W)
Location as "NE/CNWxSWx" or footage from lines SE SE
Lease Owner Nadel & Gussman
Lease Name Coberly Well No. 1
Office Address 1714 First Nat'l. Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 20, 1971 19
Application for plugging filed September 19, 1971 19
Application for plugging approved September 19, 1971 19
Plugging commenced September 20, 1971 19
Plugging completed September 20, 1971 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4405 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	244'	8 5/8		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 1100' w/100 sacks cement
Plugged through drill pipe @ 275' w/20 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this _____ day of _____, 19____
August 5, 1975
Virginia S. Fabian
Notary Public.

15-063-20084-00-00

WELL LOG

NADEL & GUSSMAN
1714 First Nat'l. Bldg.
Tulsa, Oklahoma 74103

#1 COBERLY
SE SE Sec. 15-13-27W
Gove County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 244' of 8 5/8"
w/170 sacks cement

COMMENCED: 9/10/71
COMPLETED: 9/20/71

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Shale	0	250	2465 Gr.
Shale	250	625	2467 D.F.
Sand & Shale	625	1976	2470 K.B.
Anhydrite	1976	2032	
Shale & Shell	2032	2680	
Lime & Shale	2680	3845	
Lime	3845	4405	
Total Depth	4405		

<u>FORMATION TOPS:</u>		
Anhydrite	1988 +	482
Heebner	3686 -	1216
Toronto	3713 -	1243
Lansing	3729 -	1259
Ft. Scott	4210 -	1740
Cherokee Shale	4234 -	1764
Mississippi	4305 -	1835
T. D.	4405	

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1971
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SE of Section 15-13-27W, Gove County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson

Jim Robinson

Subscribed and sworn to before me this 22nd day of September, 1971

Virginia S. Fabian

Virginia S. Fabian, Notary Public



MY COMMISSION EXPIRES:
August 5, 1975