

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER. 15-063-21,155 -00 -00

LEASE NAME Jacobs

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR Thunderbird Drilling, Inc.

SEC. 34 TWP. 13 RGE. 27 (W)

ADDRESS P.O. Box 18407, Wichita, KS 67218

COUNTY Gove

PHONE#(316) 685-1441 OPERATORS LICENSE NO. 5131

Date Well Completed 10-13-87

Character of Well D & A

Plugging Commenced 10-13-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-13-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Sent to operator for completion Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	328	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pump heavy mud to 2100'-2000', 25 sx; pump heavy mud to 1110'-710', 100 sx & 1 sx floccel;  
pump heavy mud to 330'-170', 40 sx; pump heavy mud to 40' to solid bridge-10 sx & wiper  
plug; rathole-15 sx; 60/40 posmix, 6% gel, 3% c.c. State plugger Gilbert Balthazar.  
Cement by Allied.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Agent

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 DESCRIBED AND SWORN TO before me this 2nd day of November, 19 87

Clarice M. Mize  
 Clarice M. Mize Notary Public



NOV 3 1987  
 11-03-87  
 Commission Expires November 28, 1988