


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Gove County. Sec. 33 Twp. 13S Rge. 27W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SW NE SW
Lease Owner Suburban Propane Gas Corporation
Lease Name JENSEN BEOUGHER Well No. #1
Office Address P.O. Box 17689, San Antonio, TX 78217
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed February 13 1981
Application for plugging filed February 13 1981
Application for plugging approved February 13 1981
Plugging commenced February 13 1981
Plugging completed February 13 1981
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. @ 4450
Set 1st Plug @ 980' with 60 sx.
Set 2nd Plug @ 240' with 30 sx.
Set 3rd Plug @ 40' Solid Bridge with 10 sx.
Rathole with 5 sx., 50-50 posmix, 6% gel.

Plug was down @ 4:00 p.m., 2/13/81
State Plugger - Marion Schmidt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec./Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 81

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



FEB 20 1981

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: Suburban Propane Gas Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: JENSEN BEOUGHER #1
 LOCATION: SW NE SW, Section 33-13S-27W
 Gove County, Kansas
 SPUD DATE: 2/03/81
 COMPLETION DATE: 2/13/81

0	1930	Sand & Shale
1930	3800	Shale
3800	4020	Shale & Lime
4020	4123	Lime
4123	4130	Lime & Shale
4130	4151	Lime
4151	4295	Lime & Shale
4295	4450	Lime
	4450	Rotary Total Depth

Spud hole @ 6:30 p.m., 2/03/81. Drilled 80' of a 12 1/4" hole. Lost circ. @ 70'. Cemented lost circ. zone from 80' to surface with 50 sx. of common 2% gel, 3% c.c. Commence drilling @ 11:00 a.m., 2/04/81. Drilled 254' of a 12 1/4" hole. Ran 7 jts. of 8 5/8" - 24# casing (tally 244.53') Set @ 251'. Cemented with 190 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 7:30 p.m., 2/04/81.

T.D. @ 4450'. Set 1st Plug @ 980' with 60 sx. Set 2nd Plug @ 240' with 30 sx. Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx. Job was completed @ 4:00 p.m., 2/13/81. 50-50 posmix, 6% gel. State Plugger - Marion Schmidt.

SAMPLE TOPS:

Anhydrite 2055'
 B/Anhydrite 2096'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Asst. Sec./Treas. of the Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the JENSEN BEOUGHER #1, SW NE SW, Section 33-13S-27W, Gove County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 18th day of February, 1981.

2/14/85

NOTARY PUBLIC

Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public

FEB 20 1981

CONSTRUCTION DIVISION
 KANSAS

