


15-063-20101-00-00 24

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Gove County, Sec. 36 Twp. 13S Rge. XEX 14 (W)  
Location as "NE/CNW%SW%" or footage from lines C. SW. NW  
Lease Owner Pickrell Drilling Company  
Lease Name Bird "F" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Feb. 9 19 72  
Application for plugging filed Feb. 9 19 72  
Application for plugging approved Feb. 9 19 72  
Plugging commenced Feb. 9 19 72  
Plugging completed Feb. 9 19 72  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4435 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 1025' w/100 sacks, Middle Plug @ 275'  
w/40 sacks, Top Plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 14th day of February, 19 72

My commission expires

January 19, 1973



Esther Lamone  
Notary Public.

ROTARY DRILLING LOG

15-063-20101-00-00 <sup>dy</sup>

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 1/29/72

Rotary Drilling Completed 2/9/72

LOCATION: Bird "F" No. 1, C SW NW Sec. 36-13S-27W  
Gove County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 245' KB. Cemented w/150 sacks cement. Completed 4:45 P.M. Circulated.

No oil string run. D & A. Plugged 2:45 P.M. February 9, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

100	Clay, Post Rock		
210	Shale & Shells		
1030	Shale	C. F. S.	
1080	Sand	3775	4060
1640	Shale	3875	4075
1850	Sand	3900	4100
2055	Shale	3914	4310
2100	Anhydrite	3926	4330
2345	Shale	3967	4400
2630	Shale & Lime Stringers	3980	4410
2790	Shale & Lime	3990	4420
3080	Lime & Shale	4012	4435
3150	Shale & Lime	4045	
3675	Lime		
3762	Lime & Shale		
3795	Shale & Lime		
3880	Lime	S. L. M.	
3900	Lime & Shale	Strap 3785.26	
4005	Lime	Board 3784.60	
4012	Lime & Shale		.66 Difference
4035	Lime		
4075	Lime & Shale		
4100	Shale & Lime		
4160	Lime & Shale		
4280	Lime		
4400	Lime & Shale		
4435	Miss., RTD		

Slope Tests

RECEIVED  
STATE CORP. REGISTRATION COMMISSION  
FEB 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By *C. W. Sebitts*  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 14th day of Febru<sup>ry</sup>, 1972, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

*Esther Lamone*  
ESTHER LAMONE Notary Public