


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Gove County, Sec. 23 Twp. 13 Rge. 30 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. NW SE SE
Lease Owner O.A. Sutton Oil Properties & Investments
Lease Name Steckel Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced ~~8-9-58~~ 8-9-58 19____
Plugging completed 8-10-58 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4576 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------------------|-----------------|------------|
| | | | | 8-5/8" | 198' | |
| | | | | 8-5/8" | 198' | none |
| | | | | 5-1/2" | 4210' | 1317' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4220' and found it open. Filled w/sand to 4200' and dumped 4 sacks of cement. Pulled 5 1/2" casing. Cleared hole and mudded to 600', set rock bridge and ran 20 sacks of cement. Mudded to 210', set 10' rock bridge and ran 20 sacks of cement. Mudded to 40' set 10' rock bridge and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of Augst, 19 58

My commission expires 9-27-58 TH Thomas V. Daggin Notary Public.

PLUGGING
FILE SEC 23 T 13 R 30W
BOOK PAGE 116 LINE 39

08-20-1958
CONSERVATION DIVISION

WELL LOG

15-063-00219-00-00

COMPANY O. A. Sutton
FARM Stackel NO.

SEC. 11
LOC.

TOTAL DEPTH 4516'
COMM. 11-3-55
COMP. 11-20-55

COUNTY KANSAS

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

SHOT OR TREATED
CONTRACTOR
ISSUED

ELEVATION 2574 D.F.

PRODUCTION

CASING

20 12 6-5/8" - 198'
15 8
12 6 5-1/2" - 4210'
13 5

FIGURES INDICATE BOTTOM OF FORMATIONS


- 0 - 90 Sand
- 90 - 180 Sandy blue shale
- 180 - 198 Shale and Shells
- 198 - 1075 Sandy shale, and shells
- 1075 - 1515 Shale and Shells
- 1515 - 1705 Sand
- 1705 - 1835 Shale and Lime
- 1835 - 1860 Lime
- 1860 - 2225 Shale and Lime
- 2225 - 2290 Shale and shells
- 2290 - 2335 Anhydrite
- 2335 - 2360 Shale
- 2360 - 2615 Shale and Lime
- 2615 - 3925 Lime and Shale
- 3925 - 4454 Lime
- 4454 - 4573 Cherty Lime
- 4573 - 4575 Lime and Chert
- 4575 - T.D.

GEOLOGIC TOPS:

- Anhydrite 2290'
- Topoka 3527'
- Harbner 3876'
- Toronto 3897'
- Lansing 3914'
- Mississippi 4495'

PLUGGING
NOV 23 1955 R 30W
BOOK PAGE 116 LINE 39

NOV 19 1955



State of KANSAS
County of SEDGWICK
J. Fred Hambright

Lewis Drilling

I, _____ of the _____ Company
Stackel #1
upon oath state that the above and foregoing is a true and correct copy of the log of the _____ well.

J. Fred Hambright
55

Subscribed and sworn to before me this 28th day of November 1955

My Commission Expires: August 20, 1955

Arthur R. Derrington
NOTARY PUBLIC
(Arthur R. Derrington)