



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Naab of Rains & Williamson Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Naab guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Inc. & Bill J. Porter,

Complete Address: 435 Page Court, Wichita, Kansas.

Lease Name: Mendenhall Well No. 1

Location: SW-SW-SE Sec. 21 Twp. 13 Rge. (E)(W) 28

County: Gove Total Depth 4693' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Naab was instructed to plug the well as follows:

346'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1115' and displace 110 Cu. Ft. cement thru DP. Pull DP to 375' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent