

15-063-20093-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Nadel and Gussman,

Complete Address: 514 Union Center Building, Wichita, Kansas.

Lease Name: Bethel Well No. 1

Location: 150' NW of CNW-NE Sec. 1 Twp. 13 Rge. (E)(W) 28

County: Gove Total Depth 4395' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

242'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent