

State of Kansas



15-063-20020-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
NOV 29 1967
11-29-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Woods of Sun Oil Company, has this
date requested permission to plug the following described well:

Mr. Woods guarantees payment of the plugging fee.

Operator's full Name: Sun Oil Company,

Complete Address: Box #3383, Tulsa, Oklahoma.

Lease Name: Project # 2, Well No. _____

Location: E/2 Sec. 5 Twp. 13 Rge. (E)(W) 29

County Gove Total Depth 1700 Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Woods was instructed to plug the well as follows:

320'--7" OD Surface pipe, cement circulated with 100 Sx. (6 1/4" hole).
Dakota section from 1460' to 1000'.

Circulate hole with heavy mud. Pull DP to 1485' and displace 100 Sx.
cement thru DP. Pull DP to 360' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent