

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,9260000

LEASE NAME Beery

WELL NUMBER 4

4,290 Ft. from S Section Line

4,290 Ft. from E Section Line

SEC. 4 TWP. 13 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 5-19-96

Plugging Commenced 5-19-96

Plugging Completed 5-19-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, Kansas 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-19-96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

*PCWD
05-30-96*

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	211'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Push bridge plug to 1,160', pump 25 sax cement down drill pipe. Push bridge plug to 600', pump 100 sax cement down drill pipe. Push bridge plug to 265', pump 40 sax cement down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Plug down at 6:15AM
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS: 67665

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 96

My Commission Expires: _____



Duck Phillips
Notary Public




Shields

Russell, Kansas

WELL LOG

Operator: R.P. Nixon Operations, Inc.
 Well: Beery #4
 Commenced: May 13, 1996
 Completed: May 19, 1996
 Contractor: Shields Drilling Co.

Well Description: SE NW NW
 Sec. 4-13S-16W
 Ellis County, KS.



Elevation: 1,998' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	211'	Cmtd. w/140 sax

15.051.24926.00.00

..... Figures Indicate Bottom of Formations

Shale	214'	
Shale & sand	1,143'	
Anhydrite	1,183'	
Shale	1,470'	
Sand & shale	1,865'	
Shale	2,605'	
Shale & lime	2,990'	
Lime	3,510'	RTD

15.051.24926.00.00
 15.051.24926.00.00
 15.051.24926.00.00