


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-051-01095-02-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Ellis County, Sec. 4 Twp. 13S Rge. (E) 16(W)
Location as "NE/CNWxSWx" or footage from lines NE SW NW
Lease Owner Tennessee Gas Transmission Company
Lease Name Frank Froalich Well No. 1
Office Address P.O. Box 513, Chase Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-7 1956
Application for plugging filed 11-13 1956
Application for plugging approved (oral) 11-7 1956
Plugging commenced 11-6 1956
Plugging completed 11-7 1956
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S.S. Greider
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"OD	199'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud:
Set Halliburton plug and 1/2 sack hulls at 190';
Filled hole through Drill pipe with 20 sacks
cement, then with heavy mud; 1/2 sack hulls and Halliburton
plug to 40'; Mixed 10 sacks of cement and filled
to cellar.
Plugging completed 2:00 A.M. 11-7-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Sterling Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Glen E. Armour (employee of owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of November, 1956

My commission expires May 20 1958

Clarence O. Gray
Notary Public.

PLUGGING
FILE SEC 4 T. 13 R. 16W
BOOK PAGE 114 LINE 37

NOV 14 1956
CONS. DIVISION
WICHITA, KANSAS

500

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG-----15:05:01.095:00:00-----FIDUCIARY #71

Location: NE SW 1/4, Section 4-13S-20E,
Ellis County, Kansas

OWNER: Tennessee Gas Transmission Company, et al.
ROBARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 10-24-56

COMPLETED: 11-7-56

TOTAL DEPTH: 3520'

LOG

CASING RECORD

0-201	Shale & Sand
201-700	Shale
700-770	Sand
770-830	Shale & Red Bed
830-1125	Shale & Shells
1125-1160	Anhydrite
1160-1700	Shale & Red Bed
1700-1795	Shale & Shells
1795-1930	Limestone & Shale
1930-2115	Limestone
2115-2600	Shale & Limestone
2600-2815	Shale
2815-2950	Shale & Limestone
2950-3165	Limestone
3165-3215	Limestone & Shale
3215-3473	Limestone
3473-3485	Shale & Limestone
3485-3520	Limestone

Set 2-5/8" casing at 199' with 135
sacks cement, 2 1/2 calcium chloride.

T.D.

PRODUCTION

Plugged & Abandoned.

PLUGGING
 FILE SEC 4 T 13 R 16W
 BOOK PAGE 114 LINE 37