


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-063-00052-00-00

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Gove County, Sec. 31 Twp. 13 Rge. 28 (E) W (W)
NW NW NW
Lease Owner B & R Drilling, Inc.
Lease Name Johnson "E" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/12/52 19
Application for plugging filed 6/1/52 19
Application for plugging approved 6/1/52 19
Plugging commenced 6/2/52 19
Plugging completed 6/4/52 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4582 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	198	None
				5 1/2"	4505	3358

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock to 3815', dumped 4 sacks cement with dump bailer, top of cement 3785'. Mudded hole to 198', set rock bridge, dumped 15 sacks cement, top of cement 150'. Mudded hole to 35', set rock bridge, dumped 10 sacks for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 52

[Signature]
Notary Public.

My commission expires 2-8-54.

PLUGGING
FILE SEC 31 T 13 R 28
BOOK PAGE 38 LINE 8

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1952
CONSERVATION DIVISION
WICHITA, KANSAS

15-063-00052-00-00

B & R Drilling, Inc.
Johnson "E" #1

NW NW NW of Sec. 31-13--28
Gove County, Kansas

Total Depth: 4582'
Comm. 3/16/52
Comp. 4/12/52

Casing

8 5/8" Set @ 198'
5 1/2" Set @ 4505'

Cement

135 sacks of Ashgrove
100 sacks of Lone Star

Formation	Depth
Shells-shale	40
Sand-shale	160
Shale-shells	198
Shale	1035
Sand	1095
Sand-shale	1150
Sand	1260
Shale-sand	1305
Shale-sand-red bed	1520
Shells-anhydrite--red bed-shale	1560
Shale-shells-red- bed	1660
Anhydrite	1695
Shale-shells-red bed	1730
Red bed-shale	2015
Red Bed	2100
Shale-she-lls	2145
Shale-lime	3360
Lime	3445
Lime-shale	3844
Lime	3970
Lime-shale	4010
Lime	4120
Lime-shale	4441
Lime	4582'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

-----*Law City*-----

Subscribed and sworn to before me this 10th day of June, 1952.

[Signature]

Notary Public

My commission expires: 6-17-54.

RECEIVED
STATE CONSERVATION COMMISSION
JUN 12 1952
CONSERVATION DIVISION
Wichita, Kansas

FILE SEC 31-13-28
BOOK PAGE 2 LINE 8