


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Gove County, Sec. 26 Twp. 13S Rge. 28 E/W
Location as "NE/4SW/4" or footage from lines
W/2 SW NW

Lease Owner Patrick Petroleum Company
Lease Name L. W. Roberts Well No. 1
Office Address 400 One Twenty Building, Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 2/15/80 19
Application for plugging filed 2/15/80 19
Application for plugging approved 2/15/80 19
Plugging commenced 2/15/80 19
Plugging completed 2/15/80 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations. TD 4540'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	398'	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 1000' with 70 sacks
2nd plug @ 400' with 20 sacks
3rd plug @ 40' with 10 sacks
5 sacks in rathole

Job complete @ 1:15 a.m. 2/15/80

RECEIVED
FEB 22 1980
02-22-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick
James C. Remsberg, Slawson Drilling Co., Inc. (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of February, 19 80

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Patrick Petroleum Company
 400 One Twenty Building
 Wichita, Kansas 67202

LEASE: L. W. Roberts #1
 W/2 SW NW Sec. 26-13S-28W
 Gove County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 2/6/80

COMPLETED: 2/15/80

RTD: 4540'

SURFACE CASING: 8-5/8" set at 398' with 300 sx cement

0' to 400' Shale & Sand (12½" Surface Hole)
 400' to 908' Shale
 908' to 1655' Shale & Sand
 1655' to 2139' Shale & Shells
 2139' to 2169' Anhydrite
 2169' to 2239' Shale
 2239' to 3295' Shale & Lime
 3295' to 3602' Lime & Shale
 3602' to 3751' Lime
 3751' to 3892' Lime & Shale
 3892' to 4090' Lime
 4090' to 4200' Lime & Shale
 4200' to 4540' Lime
 RTD 4540'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the L. W. Roberts #1 log for Patrick Petroleum Company.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this 21st day of February, 1980

Mary Lou Taylor
 Mary Lou Taylor, Notary

RECEIVED
 FEB 29 1980

My commission expires January 17, 1981

