


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-063-00050-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Gove County, Sec. 8 Twp. 13 Rge. (E) 30 (W)
Location as "NE/CNW/SE" or footage from lines NW NW SE
Lease Owner Spector and Morganstern
Lease Name Beougher Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 2-22-52 19
Application for plugging filed July 14, 1955 19
Application for plugging approved July 18, 1955 19
Plugging commenced 7-26- 1955
Plugging completed 9-2- 1955
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production January 1955 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing Depth to top 3908' Bottom 4130' Total Depth of Well 4634' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" OD	155'	None
				5 1/2" OD	4183'	890.66 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging started 7-26-55 and completed 9-2-55. Measured in to TD and dumped in 41' of sand and 4 sacks of cement. Shot casing off at 950' and pulled pipe out of hole. Plugged well with heavy mud to 160I and set permanent rock bridge. Filled hole with heavy mud to 35' of top and dumped in 22 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address P. O. Box 221, Great Bend, Kans.

STATE OF Kansas COUNTY OF Russell, ss.
Morgenstern & Spector

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morgan Spector
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1955

My commission expires Sept 19, 1955

Notary Public.

PLUGGING
FILE SEC 8 T 13 R 30W
BOOK PAGE 134 LINE 43

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1955
09-17-1955
CONSERVATION DIVISION
Wichita, Kansas

15-063-00050-00-00


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKILES OIL CORPORATION
Farm- Beougher No. 1

SEC. 8 T. 13 R. 30W
NW NW SE

Total Depth. 4634
Comm. 12-16-51 Comp. 2-22-52
Shot or Treated.
Contractor.
Issued. 11-29-52

County Gove KANSAS



Elevation. 2839 DF

Production. 3 bbls.

Figures indicate Bottom of Formations.

sand & shells	1356
shale & shells	2390
shale & lime	3832
lime	3860
lime & shale	3897
lime	3962
lime & shale	4011
lime	4037
lime & shale	4072
lime	4233
lime & shale	4328
lime	4402
lime & shale	4494
lime	4557
lime & shale	4586
lime	4634
Total Depth	

Tops:	
Heebner	3868
Lansing	3908
Mississippi	4495

Production is from the Lansing.
w/perforation @ 4130-4079 to
4082.

PLUGGING
FILE SEC 8 T 13 R 30W
BOOK PAGE 134 LINE 43

RECEIVED
STATE COMMISSION
JUL 13 1955
STATION DIVISION
07-18-1955