

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-063-215190000

LEASE NAME PRIEFERT

WELL NUMBER #1-27

330 Ft. from (S) Section Line

2970 Ft. from W Section Line

SEC. 27 TWP. 13 RGE. 29 (E) or (W)

COUNTY GOVE

Date Well Completed 5-08-98

Plugging Commenced 5-08-98

Plugging Completed 5-08-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KANSAS CORP. CO.

LEASE OPERATOR LANDMARK ENERGY EXPLORATION

ADDRESS 1861 N. ROCK ROAD, STE. 205

RECEIVED
MAY 13 11:20
05-13-98

PHONE (316) 683-8080 OPERATORS LICENSE NO. 06113

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 8, 1998 (date)

by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? by operator if not, is well log attached?

Producing Formation na Depth to Top Bottom T.D. 4587'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	309	8 5/8"	309'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

1st plug @ 2300' w/25 sx., 2nd plug @ 1275' w/100 sx., 3rd plug @ 360' w/40 sx., 4th plug @ 40' w/10 sx., 15 sx. in rathole.

Total 190 sx. 60/40 pozmix, 6% gel 1/4# floeal per sk. ALLIED CEMENTING SERVICE

Name of Plugging Contractor L. D. DRILLING, INC. License No. 6039

Address R.R. 1 BOX 183 B GREAT BEND, KANSAS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: LANDMARK ENERGY EXPLORATION

STATE OF KANSAS COUNTY OF BARTON, ss.

BESSIE DEWERFF

(Employee of Operator) or (Operator) or (XXXXXXXX)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Bessie M. Dewerff
Bessie Dewerff

(Address) R.R. 1 Box 183 B Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 98

Rashell Patten
Notary Public
Rashell Patten

My Commission Expires: 2-2-99