

15-051-19433-0000

8-19-87

4-27-59

6 070586

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
N/2 SE, SEC. 4, T 13 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5375

feet from S section line  
feet from E section line

Operator: Hillenburg Oil Co.  
Name & Address: 11600 South Lynn Lane Road  
Broken Arrow, Ok  
Charles McMannis

Lease Name Froelich Well # A #5  
County Ellis 35.00

Well Total Depth 634 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 6 5/8" feet 634

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Box 31, 332 West Wichita, Russell, Kansas 67665

Company to plug at: Hour: 3:00 PM Day: 19 Month: August Year: 19 87

Plugging proposal received from Charles McMannis

(company name) Hillenburg Oil Company (phone) 918-455-4444

were: 6 5/8" S.P. set at 634'. Circulated with cement, amount w/N.A.

Proposal: 100 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 4 sks Hulls.

Pump in with pump truck, load and pressure csg. with cement.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 PM Day: 19 Month: August Year: 19 87

ACTUAL PLUGGING REPORT Ordered 100 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 4 sks Hulls.

Pumped in casing with pump truck. Pumped in casing 10 sks cement 3 sks Hulls and 20 sks cement. Pressure 1000 Psig. Casing ruptured in cellar. Ran 2 7/8" tubing to 341' and hit bridge. Circulated w/65 cement. Cement circulated. Total cement 95 sks.

STATE CORPORATION COMMISSION

REC 7 1987

Remarks: Cemented by Allied Cementing.

(if additional description is necessary, use BACK of this form.)

INVESTIGATE observe this plugging.

DATE 12-8-87

INV. NO. 19204

Signed Marion J. Schmidt (TECHNICIAN)

DB