

To: 6 040793
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-19-87 15-051-06694-00-00 (3-16-41) 233

API NUMBER 15- (3-16-41)
C E/2 NW SE, SEC. 4, T 13 S, R 16 W/8

TECHNICIAN'S PLUGGING REPORT
Operator License # 5375

feet from S section line
feet from E section line
Lease Name Froelich Well # 2

Operator: Hillenburg Oil Co.
Name & Address 11600 S. Lynn Lane Road
Broken Bow, Ok.

County Ellis 113.36
Well Total Depth 3488 feet
Conductor Pipe: Size feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cmt. Co. License Number
Address Russell, Kansas

Company to plug at: Hour: 1:00 PM Day: 19 Month: August Year: 19 87

Plugging proposal received from Charles Mannis

(company name) Same (phone)

were: 7" at 3239' w/60 sks; Perf at 3238' - 3381' sq 7" csg (1977) w/200 sks at 770' w/112 sks at 773' w/178sks at 800' w/150 sks at 400'. Junk in hole at 2890'. Will run tbg to plug. Ordered 375 sks 65/35 Poz, 10% Gel, 2% Lite Add. and 1/4# Flocele and 6 sks Hulls.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00 PM Day: 19 Month: August Year: 19 87

ACTUAL PLUGGING REPORT Ran tbg. to 2888'; pmpd. through tbg. 190 sks cmt. (94 bbls. slurry) Circulated to surface. Pulled tbg. to 1145', pmpd. 20 sks. cmt. (9 bbls slurry) circ. to surface; Pulled tbg. pmpd. add. 15 sks cmt. (7bbls slurry). Max Psi. 700#, S.I. 500#. Pmpd. in 10 3/4" annulus. 145 sks cmt. w/350# Hulls. Max Psi. 300# S.I. 200#.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

DATE 9-4-87

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 18046 8-19