

4-060880

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,926-0000

5-19

SE NW NW /4 SEC. 04, 13 S, 16 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5252

Lease: Beery Well # 4

Operator: R.P. Nixon Operations, Inc.

County: Ellis

Address: 207 West 12th Street
Hays, Kansas 67601

Well total depth 3510 ^{110.82} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:45 A.M. Day: 19 Month: May Year: 1996

Plugging proposal received from: Burt Beery

Company: Shields Drilling Phone: _____

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.
Arbuckle not found by RTD per drilling contractor.

FILED
KANSAS CORPORATION COMMISSION

MAY 30 1996
05-30-96

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]


CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 11:15 A.M., Day: 19, Month: May, Year: 1996

Actual plugging report:
1st. Plug at 1160' w/25 sxs. - Anhydrite 1143' - 1193'.
2nd. Plug at 600' w/100 sxs. - Dakota 293' - 593'.
3rd. Plug at 265' w/40 sxs. - Surface pipe to 211'.
4th. Plug at 40' w/10 sxs.
15 sxs in rathole.
10 sxs in mousehole.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1993 GL

I did did not [X] observe the plugging.


BX (agent)
Form CP-2/3

INVOICED
DATE JUN 05 1996
INV. NO. 45720