

4 090080

1-14-88

API NUMBER 15- 085-20,029 0080

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE/4, SEC. 34, T 6 S, R 13 W/E

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9715

Lease Name Dugan Well # 1

Operator: Shawnee Petro Inc.

County Jackson 12/1/88

Name & Address 1607 SW 37th St

Well Total Depth 3744 feet

Topeka, Kansas 66611

Conductor Pipe: Size _____ feet

913-267-5033

Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Glacier Well Service License Number 5721

Address 825 Commercial St., Emporia, Kansas 66081

Company to plug at: Hour: 8:00 am Day: 13 & 14 Month: 1 Year: 19 88

Plugging proposal received from Steve Owen

(company name) Incline Reserves, Inc. (phone) 913-267-5033

were: Set CIBP at 3375', dump 10 sacks cement on plug. Shoot off 5 1/2" csg at
at 2000', spot 25 sack plug at 2000', POH with 5 1/2" csg to 350', spot
35 sack plug at 350', POH with 5 1/2" csg to 60', circulate cement to
surface.

Plugging Proposal Received by District Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 14 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT Reshot perf. to get well to take fluid, got plug set at 2500'

put 10 sack plug at 2500', shot 5 1/2" 1540', set 25 sack plug at 1540',

loaded hole with Bentonite mud, pulled 5 1/2" to 320', 35 sack plug.

Pulled 5 1/2" to 60', set plug and cemented to surface.

Consolidated pumped cement through 5 1/2" CSG.

01-22-88

1988

Remarks: _____

INVOICED (Additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-25-88

Signed [Signature]
(TECHNICIAN)

INV. NO. 19645