

6-22

6 061556

API NUMBER 15- 063-21,210 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 20, T 13 S, R 28 W/20X

1800 feet from S section line

3880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Mendenhaul Well # 1

Operator: Abercrombie Drilling Inc.

County Gove 154.05

Name & Address 801 Union Center

Well Total Depth 4740 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227' 165 sks

Abandoned Oil Well Gas Well Input Well SWD Well U&A x

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address 801 Union Center Wichita, Ks. 67202

Company to plug at: Hour: 9:30PM Day: 21 Month: July Year: 19 88

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling Inc. (phone)

were: Order 210 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30PM Day: 22 Month: July Year: 19 88

ACTUAL REPORT 1st plug at 4682' w/20 sks

2nd plug at 2150' w/20 sks

3rd plug at 1200' w/100 sks 1 sk. F.C.

4th plug at 275' w/40 sks

5th plug at 40' w/10 sks

10 sks in rathole 10 sks in mousehole

Remarks: Allied

(If additional description is necessary, use BACK of this form.)
did not observe this plugging.

DATE 9-20-88

Signed Gilbert G. Scheck (TECHNICIAN)

INV. NO. 22278

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
09-16-88
CONSERVATION DIVISION
Wichita, Kansas