

V.

9-30

4-041516

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ⁰⁶³ ~~15-103-21,128~~ - 00-01

S2 SW SW /4 SEC. 30, 13 S, 29 W
330 feet from S section line
4620 feet from E section line

Operator license# 5316 Lease Shivley well # 1

Operator: Falcon Exploration, Inc. County Gove

Address: 155 N. Market Well total depth 4646 feet ^{150.99}
Suite 1010 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas Surface pipe 8 5/8 Inch @ 379 feet
w/210 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00P.M. Day: 30 Month: September Year: 93

Plugging proposal received from: Bill Hammock

Company: Falcon Exploration, Inc. Phone:

Were: 5 1/2" casing set @ 4604' w/135 sxs. cement. Perf. @ 4519' -
4526'. Anhy. @ 2309' - W.L.M. 4550' - T.O.F. @ 3000+. D.V. cemented
with 270 sxs. circulate.
Order 325 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 100# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:00P.M., Day: 30, Month: September, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 325 sxs.
60/40 pozmix - 10% gel with 1/4# F.C. Max. 300#. S.I. 100#.

RECEIVED
STATE CORPORATION COMMISSION

OCT 06 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did not [X] observe the plugging.

Dennis L. Hamel

DATE 10-7-93

HD

(agent)

NO. 38898