

4-061208

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-21,541-0000

SW SE NW /4 SEC. 15, 13 S, 29 W
2970 feet from S section line
3630 feet from E section line

11/22

Operator license# 32436
Operator: Triton Exploration, Inc.
Address: 5400 E. 21st - #103
Wichita, Kansas 67213

Lease: Priefert Well # B-1
County: Gove 149.83
Well total depth 4610 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 374 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: L.D. Drilling, Inc. License# 6039

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 1:30 P.M. Day: 22 Month: November Year: 1999

Plugging proposal received from: Doran Markheim

Company: L.D. Drilling, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 4:30 P.M., Day: 22, Month: November, Year: 1999

Actual plugging report:
1st. Plug at 2050' w/25 sxs cement. Anhydrite 2046' - 2060'.
2nd. Plug at 1300' w/100 sxs cement. Dakota 980' - 1280'.
3rd. Plug at 425' w/40 sxs cement. Surface pipe to 374'.
4th. Plug at 40' w/10 sxs cement.
15 sxs in rathole.

Remarks: Halliburton Cementing.
Condition of casing in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X
Plugged through TUBING, CASING. Elevation: 2805 GL
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did [] / did not [X] observe the plugging.

INVOICED
DATE 12/23/99
INV. NO. 061034

RECEIVED (agent)
KANSAS CORPORATION COMMISSION Form CP-2/3
12-09-99