

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34151
Name: Brinker Enterprises, LLC
Address 1: 216 S Marshall St
Address 2: _____
City: Glen Elder State: KS Zip: 67446 + _____
Contact Person: Lee Brinker
Phone: (785) 545-3348
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 179-21266-00-00
Spot Description: _____
W2 NE NE NE Sec. 26 Twp. 9 S. R. 26 East West
330 Feet from North / South Line of Section
524 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Sheridan
Lease Name: Transue Well #: 26-2
Date Well Completed: 10/13/10
The plugging proposal was approved on: 10/8/10 (Date)
by: Ed Schumacher (KCC District Agent's Name)
Plugging Commenced: 10/14/10 @ 8:15 am
Plugging Completed: 10/14/10 @ 11:00 am

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	236	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced cementing 10/14/10 @ 8:15 am. 1st plug: 25sx @ 2310', 2nd plug: 100sx @ 1400', 3rd plug: 40sx @ 290', 4th plug: 10sx @ 40', 30sx in the rathole. Total of 205sx of 60/40 poz - 4% gel - 1/4# per sx flo-seal. Drilling mud was placed between all stages. Plugging complete 10/14/10 @ 11:00 am, by Allied Cementing.

RECEIVED
DEC 02 2010

Plugging Contractor License #: 33575 Name: WW Drilling, LLC **KCC WICHITA**
Address 1: 233 S. 4th Address 2: PO Box 307
City: Wameeney State: KS Zip: 67672 + _____
Phone: (785) 743-6774

Name of Party Responsible for Plugging Fees: Brinker Enterprises, LLC
State of Kansas County: _____, ss.
LEE BRINKER Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Lee Brinker