

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 8914
Name: H & C Oil Operating, Inc.
Address 1: P.O. Box 88
Address 2: _____
City: Plainville State: Ks Zip: 67663 + 0086
Contact Person: Charles Ramsey
Phone: (785) 434-7434

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

----- Depth to Top: ----- Bottom: ----- T.D. -----
----- Depth to Top: ----- Bottom: ----- T.D. -----
----- Depth to Top: ----- Bottom: ----- T.D. -----

GPS KEY

API No. 15 - 053-21013-00-00
Spot Description: N/2 SE NW
Sec. 11 Twp. 17 S. R. 10 East West
~~3680~~ 3554 Feet from North / South Line of Section
~~3300~~ 3319 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW

County: Ellsworth
Lease Name: Snyder- Frevert Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 11-9-10
Plugging Completed: 11-10-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	377'	None
			5-1/2"	3113'	1680'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 2900' and 5 sacks cement. Cut casing loose @1680', pulled up to 1300', pumped 35 sacks cement, pulled up to 950', pumped 35 sacks cement, pulled up to 430' and circulated 110 sacks cement to surface. Used 60/40 Poz, 4% gel. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2943

Name of Party Responsible for Plugging Fees: H & C Oil Operating, Inc.
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well.
(Print Name)

DR

RECEIVED
DEC 03 2010

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso