

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

REVISED

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33051
Name: C.D.OIL, Inc.
Address 1: 3236 Virginia Rd
Address 2: _____
City: Wellsville State: Ks Zip: 66092 + _____
Contact Person: Carl (Clay) Hughes
Phone: (913) 963-9127
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: 25207 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Squirrel Depth to Top: 661 Bottom: 668 T.D. 708
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 121-20078-00-01
Spot Description: _____
SE NW NW NW Sec. 1 Twp. 16 S. R. 21 East West
4,739 Feet from North / South Line of Section
4,924 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Miami
Lease Name: Mosher Well #: 1-OW
Date Well Completed: 1969
The plugging proposal was approved on: 12/2/10 (Date)
by: Steve Korf (KCC District Agent's Name)
Plugging Commenced: 12/3/10
Plugging Completed: 12/3/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
squirrel 661-668	oil	surface	8"	20'	0
		production	4 1/2"	708'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" pipe into well, could not get below 520'. Received approval from KCC field man, Taylor Herman, to plug hole from 520' to surface. Consolidated Oil Well Services hooked pump truck to 1" pipe and filled hole to surface with 40 sacks of 50/50 poz mix cement with 6% gel. Pulled 1" out of hole. Hooked pump truck to casing and pressured 5 additional sacks of cement into hole and pressured up to 800 pounds.

RECEIVED

JAN 03 2011

1-23-11
KCC WICHITA

Plugging Contractor License #: 33961 Name: Consolidated Oil Well Services
Address 1: 1322 S. Grant PO Box 884 Address 2: _____
City: Chanute State: Ks Zip: 66720 + _____
Phone: (620) 431-9210
Name of Party Responsible for Plugging Fees: C D OIL, Inc.
State of Kansas County, Franklin, ss.
Carl C. Hughes Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Carl C. Hughes



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 27264
LOCATION Ottawa
FOREMAN Alan Maden

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-03-10	3532	Masher 1-0W	NW 1	16	21	MU
CUSTOMER C.D O:1						
MAILING ADDRESS 3236 Virginia Rd						
CITY Wellsville		STATE KS	ZIP CODE 66092			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			516	Alan M	Safety Meeting	
			308	Ken H	KH	
			548	Harold J	HJD	

JOB TYPE plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2
CASING DEPTH 510 DRILL PIPE _____ TUBING 1" 510 OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE 1 bag

REMARKS: Held safety Meeting. Established date down 1" Mixed & pumped 30sk 50/50 p02 690 gal. Pulled half of 1" Filled to surface with 40 sk. Injctd 5 sk down 4 1/2. Pressured to 800 PSI

45 sk Total

Highs water

Alan Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405N		PUMP CHARGE		725.00
5406	<u>20</u>	MILEAGE		73.00
5402	<u>510'</u>	<u>Casing Footage</u>		<u>375.00</u>
5407	<u>min</u>	<u>ton miles</u>		
1118B	<u>227#</u>	<u>gel</u>		<u>45.40</u>
1124	<u>42 sk</u>	<u>50/50 p02</u>		<u>45.40</u>
				RECEIVED
				JAN 03 2011
				KCC WICHITA
				WD # <u>238409</u>
SALES TAX				<u>34.63</u>
ESTIMATED TOTAL				<u>1806.31</u>

Revin 3737

AUTHORIZATION Clay TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

C D OIL, INC. Operator #33051
3236 Virginia Rd.
Wellsville, Kansas 66092
913-963-9127

December 23, 2010

Kansas Corporation Commission
130 S. Market, Room 2078
Wichita, Ks. 67202

Re: Mosher 1-OW
API #: 15-121-20078-00-01
Sec. 1-16-21E

Dear KCC Staff,

The Well Plugging Record CP-4 form for the Mosher 1-OW that I mailed on 12/17/10 was incorrect. Enclosed is a revised copy of this form.

If you have any questions please call me at 913-963-9127.

Sincerely, *Clay Hughes*

Clay Hughes

RECEIVED
JAN 03 2011
KCC WICHITA