

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Contact Person: Dennis Kirmer  
Phone: (785) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
K.C. Depth to Top: 3744 Bottom: 3958 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 065-20772-0002  
Spot Description: \_\_\_\_\_  
SE SW NE Sec. 34 Twp. 9 S. R. 23  East  West  
2,970 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Graham  
Lease Name: Law B Well #: 5  
Date Well Completed: 9/75  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 8-19-10  
Plugging Completed: 8-19-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>K.C.</u>	<u>Oil/Water</u>	<u>Surface</u>	<u>8 5/8</u>	<u>182</u>	
		<u>Production</u>	<u>4 1/2</u>	<u>4004</u>	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech. Shoot two holes each at 2025' and 1300'. Run tubing to 2450'. Rig up Allied Cementing. Spot 180 sxs 60/40 poz 4% gel. Pull tubing to 1280'. Mix 50 sxs 60/40 poz 4% gel w 200# hulls. Pull tbg to 611'. Mix 85 sxs 60/40 poz 4% gel w/250# hulls- had cement circ to surface in 4 1/2 csg. Pull tbg out of hole. Wait two hours. Mix 85 sxs cement down 4 1/2 csg to fill 4 1/2 csg. Hook up to 8 5/8 surface pipe. Mix 100 sxs cement w/ 50# hulls- max press 50#. Shut in csg and surface pipe. Rig down, move off. Well plugged 1:30 P.M. Witnessed by Rich Williams, Hays KCC.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Phone: (785) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  
(Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JAN 24 2011

KCC WICHITA