

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Contact Person: Dennis Kirmer  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Tarkio Depth to Top: 2294 Bottom: 2370 T.D. \_\_\_\_\_  
Plattsmouth Depth to Top: 2794 Bottom: 2797 T.D. \_\_\_\_\_  
Toronto Depth to Top: 2860 Bottom: 2865 T.D. \_\_\_\_\_  
K.C. 2907 2955  
ARBUCKLE 2982 3025

API No. 15 - 167-02256-00-00  
Spot Description: \_\_\_\_\_  
N/2 SE SW Sec. 19 Twp. 14 S. R. 13  East  West  
4,290 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Ehrlich Well #: 4  
Date Well Completed: 5/41  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 8-16-10  
Plugging Completed: 8-16-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Tarkio	Oil/Water	Surface	10 3/4	232	
Plattsmouth	Oil/Water	Production	5 1/2	2982	
Toronto	Oil/Water				
K.C.	Oil/Water				
<u>ARBUCKLE</u>	<u>Oil/Water</u>				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech, shoot 2 holes each at 1050', 700', 420' and 200'. Run tubing open ended tag at 1995', pull 1 joint to 1964'. Pump 50 sx 60/40 pos 4% gel followed with 90 sx 60/40 4% gel and 300# hulls. Pull tubing to 999' pump 50 sx 60/40 pos 4% gel and 100# hulls cement, circulated to surface on 5 1/2. Pull tubing. Hook to 5 1/2 pump 60 sx 60/40 pos 4% gel circulated cement to surface on 10 3/4. witnessed by Ray Dinkel KCC Hays.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JAN 24 2011

KCC WICHITA