

ORIGINAL

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2008 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5208 Name: ExxonMobil Corporation Address 1: PO Box 4358 Address 2: City: Houston State: TX Zip: 77210-4358 Contact Person: Octavio Morales Phone: (620) 356 7531 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filled? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 189-00564-0001 Spot Description: SESENW Sec. 22 Twp. 34 S. R. 36 East West Foot from 2540284 South Line of Section Foot from 25402140 East Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Stevens Lease Name: Bevan Well #: 1 Date Well Completed: 4-13-47 The plugging proposal was approved on: 11-9-10 (Date) by: J. MacLiskey (KCC District Agent's Name) Plugging Commenced: 11-16-10 Plugging Completed: 11-17-10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Pulled Out). Handwritten entries: 10 3/4, 734, 7, 2623.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 3/8 tubing cut @ 1830. Ran 2 3/8 to 1830. Circ hole + mixed 200 lb. hulls + 60 sx cmt. in 7" from 1830 to 1600. Pull 2 3/8 to 1000. Tag plug @ 1480. Circ. hole w/mud. Pull to 760. Mixed 50 sx plug 760 to 510 10 sx 50 to 0 Cut off 10 3/4 + 7 + capped 7 3 ft below G.L.

Plugging Contractor License #: 31151 Name: Sargent And Horton Plugging Inc. Address 1: Rt 1 Box 49BA Address 2: City: Tyrone O State: OK Zip: 73951 + 9731 Phone: (580) 854 6515 Name of Party Responsible for Plugging Fees: EXXONMOBIL PROD. CO. State of Kansas County: Grant ss. (Octavio D Morales) (Print Name) Employee of Operator or Operator of above described well?

RECEIVED JAN 26 2011 KCC WICHITA

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God. Signature: Octavio D Morales