

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco LLC  
Address 1: 2020 N Bramblewood St  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + \_\_\_\_\_  
Contact Person: Emma Richmond  
Phone: ( 316 ) 265-3311  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
B \_\_\_\_\_ Depth to Top: 3738' Bottom: 3742' T.D. \_\_\_\_\_  
J \_\_\_\_\_ Depth to Top: 3859' Bottom: 3862' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 039-20386-0001  
Spot Description: NE NE SE  
NE NE SE Sec. 11 Twp. 2 S. R. 30  East  West  
2,200 Feet from  North /  South Line of Section  
440 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Decatur  
Lease Name: Elwood Well #: 2  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 9/3/2010 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 8/25/2010  
Plugging Completed: 8/26/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
B	oil/water	Surface	8 5/8"	299'	0
J	oil/water	Production	4 1/2"	3971'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf at 2450-51' and 1800-01' at 2 SPF. Spot 5 sacks gel, 50 sacks 60/40 poz cement 4% gel, 200# hulls @ 3503'. Trip out to 2565'. Pump 125 sacks cement, 100# hulls. Trip out to 1000'. Pump 125 sacks of cement. Circ cement inside of casing up to pit. TOH with tbg. Top off csg with 30 sacks. Tie onto 8 5/8. Pump 70 sacks down 4 1/2 x 8 5/8 annulus. ISIP 200".

DR

Plugging Contractor License #: 34318 Name: Berexco LLC  
Address 1: 2020 N. Bramblewood St. Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + \_\_\_\_\_  
Phone: ( 316 ) 265-3311  
Name of Party Responsible for Plugging Fees: Berexco LLC  
State of Sedgwick County, Kansas, ss.  
Dana Wreath  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dana Wreath

RECEIVED

DEC 30 2010

KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# ALLIED CEMENTING CO., LLC. 035443

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley, KS

DATE <u>8/24/10</u>	SEC. <u>11</u>	TWP. <u>20</u>	RANGE <u>30</u>	CALLED OUT	ON LOCATION	JOB START <u>12:30</u>	JOB FINISH <u>1:30</u>
LEASE <u>Elwood</u>	WELL # <u>2</u>	LOCATION <u>Oberlin W to Traer Rd, 3N 1 1/2 W</u>		COUNTY <u>DeCATUR</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)		<u>NO E &amp; N INTO</u>					

CONTRACTOR Beresco  
 TYPE OF JOB PTA  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TUBING SIZE 2 3/8 DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER Same

CEMENT  
 AMOUNT ORDERED 400 SK, 60/40  
400 gel 400 lb Halls on side  
5 gal on side  
 COMMON 240 @ 15.45 3708.00  
 POZMIX 160 @ 8.00 1280.00  
 GEL 19 @ 20.00 395.00  
 CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_  
 ASC \_\_\_\_\_ @ \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK CEMENTER Alan  
 # 422 HELPER Wayne  
 BULK TRUCK  
 # 394 DRIVER Brandon  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

Halls 85K, 400 lb @ 31.25 254.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

HANDLING 422 @ 2.40 1024.80  
 MILEAGE 10.4 SK/mile 2989.00  
 TOTAL 9651.80

**REMARKS:**

MIX 55K gel Tail w/ 50 SK, 60/40 490  
w/ 200 lb Halls @ 3500. Pull to 2450  
MIX 125 SK, 60/40 490 w/ 100 lb Halls  
Pull to 1000 ft, Circulate Cement to Surface  
w/ 125 SK, 60/40 490 gel w/ 100 lb Halls  
Pull out of hole, top off w/ 30 SK.  
MIX 70 SK, down B-side to 200 psf.

Thank You Alan, Wayne, Brandon

CHARGE TO: Beresco Inc  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB 35  
 PUMP TRUCK CHARGE 1185.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 70 Miles @ 7.00 490.00  
 MANIFOLD @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

TOTAL 1625.00

**PLUG & FLOAT EQUIPMENT**

RECEIVED  
 DEC 30 2010  
 KCC WICHITA

TOTAL \_\_\_\_\_

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_  
 SIGNATURE Alan

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.