

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 7030
Name: John Roy Evans Oil Company, LLC
Address 1: P.O. Box 385
Address 2: _____
City: Clafin State: KS Zip: 67525 + 0385
Contact Person: Gary Kirmer
Phone: (620) 793-2026
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 3257 Bottom: 3259 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 053-20987-0000
Spot Description: _____
100E SW NW SW Sec. 29 Twp. 17 S. R. 10 East West
1,850 1660 Feet from North / South Line of Section
4,950 4835 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellsworth
Lease Name: Janssen Well #: 1
Date Well Completed: 3/31/1986
The plugging proposal was approved on: 10/27/2010 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 10/28/2010
Plugging Completed: 10/29/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing/KC 2947-3216	oil/water	surface	8 5/8"	301'	
Arbuckle 3246-3289	oil/water	production	5 1/2"	3288'	

RECEIVED
DEC 14 2010
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10/28/2010 Sanded off perfs to 3150'. 5 sx cement on top of sand with glass bottom bailer.
10/29/2010 Shot off csg @ 1483'. Pulled to 1300'.
Mixed 35 sx 60/40 poz, 4% gel @ 1300'. Mixed 35 sx 60/40 poz, 4% gel @ 950'. Mixed 130 sx 60/40 poz, 4% gel @ 350' and circulated cement to surface. Pulled remaining csg and topped well off.

Plugging Contractor License #: 6901 Name: D.S.&W Well Servicing, Inc.
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Phone: (620) 793-5838
Name of Party Responsible for Plugging Fees: John Roy Evans Oil Company, LLC
State of Kansas County: Barton , ss.
Gary Kirmer Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Kirmer