

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33699  
Name: T-N-T ENGINEERING, INC  
Address 1: 9250 E COSTILLA AVE STE 510  
Address 2: \_\_\_\_\_  
City: ENGLEWOOD State: CO Zip: 80112 + \_\_\_\_\_  
Contact Person: ANN VERZELETTI  
Phone: (303) 704-1539  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L: KC Depth to Top: 3068 Bottom: 3080 T.D. 3406  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-22944-00-00  
Spot Description: SW/4  
NE NE SW SW Sec. 9 Twp. 15 S. R. 13  East  West  
3960 1251 Feet from  North /  South Line of Section  
1320 4040 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: RUSSELL  
Lease Name: ROESNER Well #: 17  
Date Well Completed: 11/1990  
The plugging proposal was approved on: 12/06/2010 (Date)  
by: RAY DINKLE (KCC District Agent's Name)  
Plugging Commenced: 12/07/2010  
Plugging Completed: 12/07/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8-5/8"	566	0
		PRODUCTION	5-1/2"	3431	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf squeeze hole @ 1500', 830', 560' & 200'. 1st plug @ 3343', 10 sx gel, 75 sx cement & 100# hulls. 2nd plug @ 1488', 100 sx cement & 100# hulls. 3rd plug @ 744', 140 sx cement w/ cement to surface csg & surface. Topped off csg w/ 25 sx cement, total cement used 340 sx 60/40 poz 2% gel & 200# hulls.

Plugging Contractor License #: 6123 Name: CHASE WELL SVC  
Address 1: PO BOX 355 Address 2: \_\_\_\_\_  
City: GREAT BEND State: KS Zip: 67530 + \_\_\_\_\_  
Phone: (620) 793-9556  
Name of Party Responsible for Plugging Fees: T-N-T ENGINEERING, INC  
State of KANSAS County, BARTON, ss.  
RICKEY POPP (AGENT)  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rickey Popp

RECEIVED  
DEC 14 2010

KCC WICHITA

DR