

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5039  
Name: AGV Corp.  
Address 1: PO Box 377  
Address 2: \_\_\_\_\_  
City: Attica State: KS Zip: 67009 + \_\_\_\_\_  
Contact Person: Kent Roberts  
Phone: (316) 215-1683  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
White Cloud Depth to Top: 2059 Bottom: 2063 T.D. 2410  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 191-22411-00-00  
Spot Description: \_\_\_\_\_  
\_\_\_\_\_- SE SW Sec. 13 Twp. 32 S. R. 4  East  West  
760 Feet from  North /  South Line of Section  
2,080 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Sumner  
Lease Name: Weishaar Well #: 1-13  
Date Well Completed: 9/1/2003  
The plugging proposal was approved on: 12/8/2010 (Date)  
by: Steve VanGieson (KCC District Agent's Name)  
Plugging Commenced: 12/9/10  
Plugging Completed: 12/9/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface	Water	Surface	8-5/8	252'	None
		Production	5-1/2	3077'	1016

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @ 2040' w/ 2 sacks cement on top.  
Shot casing @ 1250', no recovery, Shot casing @ 1130', no recovery  
Shot casing @ 1016' and pulled.  
1st plug @ 850' w/ 35 sacks cement  
Circulated from 330' to surface w/ 100 sacks and topped off w/ 40 sacks  
Total 175 sacks 60/40 poz 4% gel

Plugging Contractor License #: 34227 Name: Amercian Well Service, LLC  
Address 1: PO Box 464 Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Phone: (620) 770-0621  
Name of Party Responsible for Plugging Fees: AGV Corp.  
State of Kansas County, Sedgwick, ss.  
Kent Roberts  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Kent Roberts

DR  
Rec'd  
12-17-10