

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3532
Name: CMX, Inc.
Address 1: 1700 N. Waterfront Pkwy
Address 2: Bldg. 300, Suite B
City: Wichita State: KS Zip: 67206 +
Contact Person: Douglas McGinness II
Phone: (316) 269-9052
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: ~~SWD Permit # 12345~~
 ENHR Permit #: E16259.1 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 4998 Bottom: 5010 T.D. 5010
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 007-01319-000
Spot Description: _____
SW NW SW Sec. 12 Twp. 35 S. R. 15 East West
980 1767 Feet from North / South Line of Section
880 4714 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Davis Ranch Well #: 3-12
Date Well Completed: _____
The plugging proposal was approved on: 12/22/2010 (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Plugging Commenced: 12/23/2010
Plugging Completed: 12/27/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	854	None
		Production	4 1/2	5009	2200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP set at 4800', CIBP set at 2800', cement retainer set at 2740', spot 4sx cement on retainer, pull 2200' casing, run tubing to 1st 870', pump 10sx gel, 50sx 60/40 POZ 4% gel, 2nd 300', 50sx 60/40 POZ, 3rd 60', 20sx 60/40 POZ, circulate to surface

RECEIVED

JAN 03 2011

Plugging Contractor License #: 5105 Name: Clarke Corporation **KCC WICHITA**
Address 1: P.O. Box 187 Address 2: 107 W. Fowler
City: Medicine Lodge State: KS Zip: 67104 +
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: CMX, Inc
State of Kansas County, Barber, ss.
Mark Morgenstern Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern