

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32446
Name: Merit Energy Company
Address 1: 13727 Noel Rd., Suite 500
Address 2: _____
City: Dallas State: TX Zip: 75240 + _____
Contact Person: Lynne Moon /Regulatory Manager
Phone: (972) 628-1569
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 5179' Bottom: 5192' T.D. 6750'
Toronto Depth to Top: 4358' Bottom: 4370' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-21661-00-02
Spot Description: S2 S2 VENE Sec. 15 Twp. 35 S. R. 34 East West
4,260 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Boles "D" Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: 12/20/10 (Date)
by: Jack MacClaskey (KCC District Agent's Name)
Plugging Commenced: 12/20/10
Plugging Completed: 12/27/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	1616'	NONE
		Production	5 1/2"	5303'	1770'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run in hole w/ tbg set CIBP # 1) set @ 5127', cap w/ 5 sks cement, POH & PU CIBP # 2) TIH & set @ 4303', release from tbg, circ hole w/ mud & cap w/ 5 sks cement. POH w/ tbg. Cut & pull 5 1/2" csg from 1770' (41 jts csg). TIH w/ tbg @ 1650' & spot 80 sks Class "C" cement, POH @ 580' & pump 60 sks Class "C" cement, top out 64' - 4' w/ 20 sks cement.

Plugging Contractor License #: 33338 Name: ORR ENTERPRISES, INC.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Merit Energy Company
State of Texas County: Dallas, ss.
CINDY CHAVEZ Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jalton Chang

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 29 2010

KCC WICHITA