

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5044
Name: WHITE PINE PETROLEUM CORPORATION
Address 1: 110 S. MAIN, STE 500
Address 2: _____
City: WICHITA State: KS Zip: 67202 +
Contact Person: WILBUR C BRADLEY
Phone: (316) 262 - 5429
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
STALNAKER Depth to Top: 3391 Bottom: 3396 T.D. 3500
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 077 21206 000X
Spot Description: C S 1/2 SW 1/4
S/2 SW Sec. 35 Twp. 32 S. R. 5 East West
660 Feet from North / South Line of Section
1320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: HARPER
Lease Name: DUNCAN Well #: 1
Date Well Completed: 05/24/91
The plugging proposal was approved on: 08/10/10 (Date)
by: STEVE VAN GIESON (KCC District Agent's Name)
Plugging Commenced: 12/15/10
Plugging Completed: 12/16/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
STALNAKER	GAS	SURFACE	8 5/8"	328	NONE
		PRODUCTION	4 1/2"	3490	1800

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND TO 3340, SPOT 4SX CEMENT, THROUGH TUBING. CIRC HOLE AT 950', PUMP 35SX CEMENT, CIRC HOLE AT 600', PUMP 35SX CEMENT, CIRC HOLE AT 380' PUMP 180SX CEMENT, CIRC CEMENT TO SURFACE - TOP OFF WITH 10SX CEMENT

RECEIVED
DEC 27 2010
KCC WICHITA

Plugging Contractor License #: 5105 Name: CLARKE CORPORATION
Address 1: P O BOX 187 Address 2: _____
City: MEDICINE LODGE State: KS Zip: 67104 + 0187
Phone: (620) 886 - 5665
Name of Party Responsible for Plugging Fees: WHITE PINE PETROLEUM CORPORATION
State of KANSAS County, SEDGWICK, ss.
WILBUR C. BRADLEY Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Wilbur C Bradley