

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003
 Name: McCoy Petroleum Corporation
 Address 1: 8080 E. Central Ave.
 Address 2: Suite #300
 City: Wichita State: KS Zip: 67206-2366
 Contact Person: Scott Hampel
 Phone: 316-636-2737

Type of Well (Check One): Oil Well Gas Well O&G D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: Bottom: T.D.
 Depth to Top: Bottom: T.D.
 Depth to Top: Bottom: T.D.

API Number: 15-039-21119-0000
 Spot Description: 120'N & 20'E of
C NE SW Sec 32 Twp 5 S. Rng. 30 East West
2100 Feet from North / South Line of Section
2000 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Decatur
 Lease Name: BASTIN TRUST "A" #1-32
 Date Well Completed: 10/11/2010
 The plugging proposal was approved on: 10/10/2010 (Date)
 by: Case Morris (KCC District Agent's Name)
 Plugging Commenced: 10/10/2010
 Plugging Completed: 10/11/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	220 260'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10/11/2010: Allied plugged hole with 220 sx 60/40 pozmix with 4% gel and 1/4#/sk floseal as follows: heavy mud in hole to bottom plug, 25 sx @ 2630', 100 sx @ 1800', 40 sx @ 300', 10 sx @ 0-40', 30 sx in rathole and 15 sx in mousehole. Plugging completed at 2:00 A.M. on 10/11/10. Orders from Case Morris, KCC.

Plugging Contractor License #: 30606 Name: Murfin Drilling Company
 Address 1: 250 N. Water St., Suite #300 Address 2:
 City: Wichita State: KS Zip: 67202
 Phone: 316-267-3241

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
 State of Kansas County, Sedgwick ss.

Scott Hampel (Vice President - Production) Employee of Operator or Operator on above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
 (Signature) Scott Hampel

RECEIVED
DEC 27 2010
KCC WICHITA