

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 30717 Name: Downing Nelson Oil Company Inc. Address 1: PO Box 372 City: Hays State: KS Zip: 67601 Contact Person: Ron Nelson Phone: (785) 621-2610 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) None Depth to Top: Bottom: T.D.

API No. 15 - 065-23,688-00-00 Spot Description: W/2 W/2 SW Sec. 11 Twp. 9 S. R. 24 East West 1,320 Feet from North South Line of Section 330 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Graham Lease Name: Rice Estate Well #: 1-11 Date Well Completed: 10/31/2010 The plugging proposal was approved on: 10/29/2010 (Date) by: Ed Schumacher (KCC District Agent's Name) Plugging Commenced: 7:15PM 10/31/2010 Plugging Completed: 10:15PM 10/31/2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface pipe, 8 5/8, 305.42, None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 2170' with 25sks, 2nd Plug @ 1300' with 100sks, 3rd Plug @ 355' with 40sks, 4th Plug @ 40' with 10sks, 30sks in rat hole and 15sks in mouse hole, total 220sks 60/40 Poz 4% Gel with 1/4# CF/sk, By Allied Cementing, Completed @ 10:15PM 10/31/2010, Circulated 1st Plug 15 minutes with 62 Vis Mud, Plugs displaced with mud.

RECEIVED DEC 09 2010

Plugging Contractor License #: 3154 Name: Discovery Drilling Co., Inc. Address 1: PO Box 763 Address 2: City: Hays State: KS Zip: 67601 + 0763 Phone: (785) 623-2920

KCC WICHITA

Name of Party Responsible for Plugging Fees: Downing Nelson Oil Company Inc. State of Kansas County, Ellis, ss. Michele Meier (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Michele Meier