

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9408
Name: Trans Pacific Oil Corporation
Address 1: 100 S Main Ste 200
Address 2: _____
City: Wichita State: KS Zip: 67202 + 3735
Contact Person: Glenna Lowe
Phone: (316) 262-3596
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 053-20043-00-00
Spot Description: SE NW SE
~~NE SW SE~~ Sec. 20 Twp. 14 S. R. 10 East West
900 1323 Feet from North / South Line of Section
1,650 1561 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellsworth
Lease Name: X Kratky Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 4/13/11
Plugging Completed: 4/18/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	200	150 Sacks Cement
		Production	4.5	2889	100 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge at 250', would not move. Bad collar, welded 4 1/2" slip collar on. Hooked up pump truck & moved bridge to 425'. Started circulating 8 5/8" casing. Ran 20 joints to 600'. Ran 91 joints to 2760' & pumped 40 sacks cement & 3 % cc. Pulled tubing out & perforated at 1200', 850' & 250'. Ran 39 joints to 1200' & pumped 35 sacks cement & 100# hulls. Pulled to 850' & pumped 35 sacks cement. Pulled to 250' & circulated 60 sacks cement to surface. Pulled tubing & topped off with 20 sacks cement. Cut off casing head 4' below ground.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Kansas County, Sedgwick, ss. Gary Sharp Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Sharp

RECEIVED

APR 28 2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA